BRUHAT BANGALORE MAHANAGARA PALIKE, YELAHANKA ZONE

Executive Engineeer
Byatarayanapura Division
B.B.M.P., Bangalore - 92

DRAFT TENDER SCHEDULE

Issued to :

Original / Duplicate

NAME OF WORK: Improvements to Roads from Amruthahalli main road to Hottappa Layout in ward No. 7 Byatarayanpura, Kodigehalli sub division

Sl. No.	Quantity.	Description	Unit	Rates	
				In Figures	In Words
1	843.2	KSRRB M300-2: Earth work excavation by manual means in Ordinary Soil involving an average horizontal throw up to 2mts and an average lift up to 0.5m, excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications complete as per specifications.	cum	75.6	
2	1488	KSRRB M300-52.1. Scarifying the existing granular road surface to a depth of 50mm and disposal of scarified material within all lifts and leads upto 1000 metres complete as per specifications.	sqm	18.36	
3	1488	KSRRB 300-58. Compaction of original ground with maximum of 6 passes of 8 to 10 tonnes power roller including filling in depression occuring during rolling including cost of all labour, HOM of machinery complete as per specifications. (	sqm	4.48	
4	89.28	KSRB 4-1.2: Providing and laying in position plain cement concrete of I mix M10 With OPC cement @ 220 Kgs with 40mm and down size graded granite metal coarse aggregates @ 0.892 cum and fine aggregates @ 0.465 cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing	cum	5064.12	
5	1256.2	KSRB 4-6.1 : Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for foundations, footings, bases of columns for mass concrete including cost of all materials, labour	sqm	236.52	
6	100.16	Providing and laying cement concrete using 20mm and down size granite jelly of ready mix concrete for RCC works laid in 15 cm thick layers and well compacted including vibrating curing etc., including smooth finish in CM 1:3, with all lead and lift etc., complete. (exculsive of cost of steel, fabrication and plastering charges)Ready mixed Cement concrete for Beams, Columns, Staircase and Roof with M-20 (1:1.5:3) (Cement-3320Kg/cum)	cum	5847.12	

7	8.01	KSRB 4.9.2 : Providing T.M.T steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery complete as per specifications. (	cum	78351.84	
8	384.4	KSRRB M400-17. Providing, laying, spreading and compacting graded stones aggregate to wet mix macadam specifications including pre mixing the material with water at OMC in mechanical mix plant carriage of mixed method of tipper to site, laying in uniform layers with paver in sub-base/base course on well prepared surface and compacting with vibratory roller to achieve the desired density complete as per specifications. (P. 154 Item No. 20.18)14-15	cum	1438.56	
9	1537.6	KSRRB M500-6. Providing and applying primer coat with bitumen emulsion on prepared surface of granular base including clearing of road surface and spraying primer at the rate of 0.60 kg / sqm using mechanical means complete as per specifications. (P. 157, Item No. 21.6)14-15	sqm	31.32	
10	76.88	KSRRB M500-18. Providing and laying dense Graded bituminous Macadum using crushed agregates of specified grading premixed with VG30grade bituminous binder and transporting the hot mix to work site , laying to the required grade , level and allignment , rolling with smooth wheeled vibratory and tandem rollers to achieve the desired compaction as per morth table 500-10 complete in all respects complete as per specification -do- using 40/60 TPH capacity H.M.P With sensor paver Gr-11 (50mm to 75mm) with 4% VG-30Bitumen	cum	7914.24	
11	1537.6	KSSRB M500 10 Providing and applying tack coat using 80/100 grade bitumen (VG10) In boiler fitted with spray set distrubuter at the rate of 0.2 kg per sqm on existing prepared bitumenous surface cleaned with mechanical broom complete as per specification pg no : 158 Item no : 21.10.2	sqm	11.88	

12	61.5	KSRRB M500-19. Providing and laying bituminous concrete Using crushed agregate of spacifying grading , premixed with bituminious binder and filler , transporting the hot mx to work site , laying with paver finisher to the required grade , level and allignment , rolling with the smooth wheeled vibrator and tandem rollers to archive the desired compaction as per MORTH specification clause no 509 complete in all respects complete as per specification -do- using 40/60 TPH capacity H.M.P with sensor paver Gr - 1 (50mmto 60mm) with 5.5% CRMB 55	cum	9483.48	
13	49.6	KSRRB M800-13.Road Marking with Hot Applied Thermoplastic Compound with Reflectrising Glass Beads on Bituminous Surface:- Providing and laying of hot applied thermoplastic compound 2.5 mm thick including reflectorising glass beads at 250 gms per sqm area, thickness of 2.5 mm is exclusive of surface applied glass beads as per IRC:35. The finished surface to be level, uniform and free from streaks and holes complete as per specifications.	sqm	475.2	
14	843.2	Lead for Disposal of Debris shall be payable at carage rates by Mechanical means inlcuding loading and unloading. From 0.00 to 5.00 Km (Page No.141)	cum	72.71	

Signature of the Contractor

Executive Engineer
Byatarayanapura Division
BBMP, Bangalore - 92

ಕರಡು ಟೆಂಡರ್ ಷಡ್ಯೂಲ್‌ನ್ನು
ಶಿದ್ದುಪಡಿಗಳ ಸಂಖ್ಯೆ.....(Nil)
ಶಿದ್ದುಪಡಿ ಮಾಡಿ/ಇಲ್ಲದೆ
ಅನುಮೋದನೆ ನೀಡಿಲಾಗಿದೆ

24/8/15